

SECTION 01 77 00

CLOSEOUT PROCEDURES

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures, including Notice of Completion and Final Inspection procedures.
 - 2. Occupancy procedures, including Notice of Approval of Occupancy/Use and University Supplemental Notice of Occupancy and Use List.
 - 3. Final Acceptance procedures, including Pre-Acceptance Checklist and University Supplemental Building/Project Acceptance List.
 - 4. Inspections after completion.
 - 5. Warranties.
 - 6. Final cleaning.
 - 7. Repair of the Work.
- B. Related Requirements:
 - 1. Section 01 32 33 "Photographic Documentation" for submitting final completion construction photographic documentation.
 - 2. Section 01 73 00 "Execution" for progress cleaning of Project site.
 - 3. Section 01 78 23 "Operation and Maintenance Data" for operation and maintenance manual requirements.
 - 4. Section 01 78 39 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
 - 5. Section 01 79 00 "Demonstration and Training" for requirements for instructing University's personnel.

1.3 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Notice of Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Acceptance.

1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.

- C. Field Report: For pest control inspection.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

1.6 NOTICE OF COMPLETION AND SUBSTANTIAL COMPLETION PROCEDURES

- A. Procedures and Submittals Prior to Notice of Completion: Complete and submit all of the following items prior to submitting Notice of Completion to Architect/Engineer. Include Contractor's comprehensive list of items to be completed, corrected or not in compliance with the Drawings and Specifications.
 - 1. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's preliminary punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
 - 2. Building Inspection Record: Submit completed record with all required corrections noted.
 - 3. Certificate of Occupancy: Submit Certificate of Occupancy (CO) or Temporary Certificate of Occupancy (TCO).
 - 4. Final Completion Schedule: Submit schedule for performing and completing all work indicated on the Contractor' list of incomplete items.
 - 5. Submit sustainable design documentation.
 - 6. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.
 - 7. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 - 8. Submit test/adjust/balance records.
- B. Final Inspection: Submit Notice of Completion to Architect/Engineer. Upon receipt, Architect/Engineer and University will review and if all items on the University Supplemental Notice of Completion Checklist are complete will, within the timeframe required by the Contract, schedule and make an inspection of the Project to determine whether the Work is substantially complete.
 - 1. Final Punch List: Based on the inspection, Architect/Engineer will prepare a final punch list of work to be completed, work not in compliance with the Drawings or Specifications, and unsatisfactory work for any reason.
 - 2. Re-inspection: If the cumulative number of items identified on the final punch list prevents a determination that the work is substantially complete, complete those items and when complete resubmit Notice of Completion. Upon receipt of resubmittal, Architect/Engineer and University will then schedule and make a re-inspection of the Project to determine whether the Work is substantially complete.
- C. Notice of Substantial Completion: When inspection of the Work indicates that the Project is substantially complete and all other Contract provisions required for substantial completion have been satisfied, Architect/Engineer will issue a Notice of Substantial Completion (State Form SBP-07).

1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor or as approved by Architect/Engineer.
 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect/Engineer.
 - d. Name of Contractor.
 - e. Page number.
 4. Submit list of incomplete items in the following format:
 - a. MS Excel and PDF electronic file. Architect/Engineer will return annotated file.

1.8 OCCUPANCY PROCEDURES

- A. Procedures and Submittals Prior to Occupancy: Complete and submit all items on both State Form SBP-01 "Notice of Approval of Occupancy/Use" and University Supplemental Notice of Occupancy and Use List.

1.9 FINAL ACCEPTANCE PROCEDURES

- A. Procedures and Submittals Prior to Final Acceptance: Complete and submit all items on both State Form SBP-05 "Pre-Acceptance Checklist" and University Supplemental Building/Project Acceptance List.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 business days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect/Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect/Engineer will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.10 SETTLEMENT AND FINAL PAYMENT

- A. Submit and complete all of the following as a condition precedent to settlement and final payment:
1. All guarantees and warranties.
 2. All statement to support local sales tax refunds, if any.
 3. Three (3) sets of operation and maintenance manuals.
 4. One (1) set of as-built Contract Documents showing all job changes.
 5. All demonstration and training completed in accordance with Section 01 79 00.

6. All punch list items documented as complete.

B. Final Certificate of Payment: Submit in accordance with the requirements of Section 01 29 00 "Payment Procedures."

1.11 INSPECTIONS AFTER COMPLETION

A. Warranty/Guarantee Inspections: During the warranty period, accompany Architect/Engineer and University Representative, and participate in inspection(s) of the Project to identify defective and deficient work at intervals and as required by the Contract.

B. List of Deficient or Defective Work: Within 10 business days of inspection, Architect/Engineer will provide Contractor with a list of items requiring correction.

C. Remedial Work: Upon receive of itemized list, immediately correct and remedy deficiencies and defects in a manner satisfactory to the Architect/Engineer and University.

1.12 SUBMITTAL OF PROJECT WARRANTIES

A. Time of Submittal: Submit written warranties to the Architect/Engineer prior to advertisement of the Notice of Contractor's Settlement. If the Notice of Acceptance designates a commencement date for warranties other than the date of Notice of Acceptance for the Work, or a designated portion of the Work, submit written warranties upon request of the Architect.

B. Partial Occupancy: When a designated portion of the Work is completed and occupied or used by the University, by separate agreement with the Contractor during the construction period, submit properly executed warranties to the Architect/Engineer within fifteen (15) calendar days of completion of that designated portion of the Work.

C. Special Warranties: When a special warranty is required to be executed by the Contractor, or the Contractor and a Subcontractor, supplier or manufacturer, prepare a written document that contains appropriate terms and identification, ready for execution by the required parties. Submit a draft to the University through the Architect/Engineer for approval prior to final execution. Refer to individual Specification Sections for specific requirements for special warranties.

D. Form of Submittal: Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.

1. Number of Copies: Two.

2. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.

3. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.

4. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

5. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.

E. Provide additional copies of each warranty to include in operation and maintenance manuals.

- F. List of Extended Warranties: Provide a comprehensive list of all manufacturers' standard and special warranties with duration greater than one year after Notice of Acceptance. Organize list into an orderly sequence based on table of contents of the Project Manual.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
 - 1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.
 - 2. Do not use sweeping compounds on concrete floors that will leave residue affecting finish floor materials.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations immediately prior to Occupancy for entire Project or for a designated portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
 - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - e. Remove snow and ice to provide safe access to building.
 - f. Clean exposed exterior and interior finishes to a dirt-free condition, free of grease, dust, stains, films, fingerprints, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
 - h. Sweep concrete floors broom clean in unoccupied spaces.
 - i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
 - j. Power scrub and power buff resilient flooring surfaces, tile and fluid-applied flooring.
 - k. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.

- l. Remove labels that are not permanent.
 - m. Wipe surfaces of mechanical and electrical equipment, elevator equipment where applicable, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
 - n. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
 - o. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
 - p. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.
 - 1) Clean HVAC system in compliance with NADCA Standard 1992-01. Provide written report on completion of cleaning.
 - q. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
 - r. Clean food service equipment to sanitary condition acceptable for intended food service use and approved by authority having jurisdiction.
 - s. Leave Project clean and ready for occupancy.
- C. Pest Control: Comply with pest control requirements in Section 01 50 00 "Temporary Facilities and Controls." Prepare written report.

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that already show evidence of repair or restoration.
 - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
 3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
 4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

3.3 ATTACHMENTS

- A. Samples of the following forms are appended to this Section for reference following End of Section 01 77 00:
 1. University of Colorado Denver | Anschutz Medical Campus Supplemental Notice of Occupancy and Use List.

2. University of Colorado Denver | Anschutz Medical Campus Supplemental Building / Project Acceptance List.

END OF SECTION 01 77 00